




Packing, handling & site work

Radiator sections are supplied on pallets to facilitate handling. They are delivered fully assembled, so no site assembly is required. Any accessories are delivered packed separately for fitting by the installer. It is important that radiators are protected from the elements during offloading and are stored in dry and adequately heated premises. After radiators have been removed from their pallets they must be kept vertical whilst being carried to their installation locations to avoid damage to the section joints.

Safe handling

Cast iron radiators are heavy. Always provide sufficient manpower to make carrying safe. Incorrect handling of radiators can cause water leaks from section joints. Lift the radiators in the centre to bring them to the vertical position before lifting and carrying. Never carry radiators stretcher fashion.



DO NOT!
Lift from one end



DO NOT!
Carry radiators flat



ALWAYS!
Lift in centre



ALWAYS!
Keep sections vertical

Guarantee

Subject to correct handling, installation, water treatment and operation, radiators are guaranteed for 10 years from date of despatch. The guarantee is not valid if the radiator sections become blocked with debris and/or carbonate deposits from the heating system or for leakage from connection joints that are not factory assembled. System water must be treated with an approved additive to remove dissolved oxygen and control the ph value.

Cast Iron Radiators

15 Ainderby Gardens, Romanby, Northallerton, North Yorkshire, DL7 8GU

Telephone: 01609 761083

E-mail: info@castironradiators.biz

Website: www.castironradiators.biz